

HOT2000

Natural Resources CANADA
Version 11.10



File: WizardHouse_Test4_basedonPerfPathC1.h2k
House

Weather Library: C:\HOT2000 v11.10b20288\Dat\Wth2020.dir
Weather Data for: EDMONTON INTL, ALBERTA

Builder Code:

Data Entry by:
Date of entry: 12/12/2023

Company:

Client name: ,
Street address:
City: EDMONTON INTL **Region:** ALBERTA
Postal code: **Telephone:**

GENERAL HOUSE CHARACTERISTICS

House type: Single Detached
Number of storeys: Two storeys
Plan shape:
Front orientation: Northeast
Year House Built: 2021

Wall colour:	Default	Absorptivity:	0.40
Roof colour:	Default	Absorptivity:	0.40
Soil Condition:	Normal conductivity (dry sand, loam, clay)		
Water Table Level:	Normal (7-10m/23-33ft)		
House Thermal Mass Level:	(A) Light, wood frame		
Effective mass fraction	1.000		

Occupants :
2 Adults for 50.0% of the time
2 Children for 50.0% of the time
0 Infants for 0.0% of the time

Sensible Internal Heat Gain From Occupants: 2.40 kWh/day

HOUSE TEMPERATURES

Heating Temperatures

Main Floor	Daytime Setpoint:	69.8 °F
	Nighttime Setpoint:	69.8 °F
	Nighttime Setback Duration:	8.0 Hours
	24 Hour Average:	69.8 °F
Basement	Setpoint:	66.2 °F
	TEMP. Rise from 69.8 °F:	9.9 °F
Basement is- Heated: No Cooled: No Separate T/S: No		
Fraction of internal gains released in basement :		0.150
Indoor design temperatures for equipment sizing		
	Heating:	71.6 °F
	Cooling:	75.2 °F

WINDOW CHARACTERISTICS

Label	Location	#	Overhang Width (ft)	Header Height (ft)	Tilt deg	Curtain Factor	Shutter (R)
Southeast							
Master Bed (P)	(2F) Main	1	0.98	4.99	90.0	1.00	0.00
Northeast							
Bed 3 (S)	(2F) Main	1	0.98	0.98	90.0	1.00	0.00
Doorlite	Front Entry	1	4.00	2.00	90.0	1.00	0.00
Ensuite (P)	(2F) Main	1	0.98	0.98	90.0	1.00	0.00
Master Bed (S)	(2F) Main	1	0.98	4.99	90.0	1.00	0.00
Northwest							
Basement (DS) 2	Foundation	1	0.98	20.01	90.0	1.00	0.00
Main Bath (P)	(2F) Main	1	0.98	0.98	90.0	1.00	0.00
Southwest							
Basement (DS) 1	Dropped Wall	1	0.98	25.00	90.0	1.00	0.00
Bed 2/ Hallway (P)	(2F) Main	2	0.98	4.99	90.0	1.00	0.00
Bed 2/ Hallway (S)	(2F) Main	2	0.98	4.99	90.0	1.00	0.00
Great Room (P)	(1F) Main Dropped	1	0.98	14.99	90.0	1.00	0.00
Great Room (S)	(1F) Main Dropped	1	0.98	14.99	90.0	1.00	0.00
Rear Doorlite	Rear Entry 2	1	0.98	14.99	90.0	1.00	0.00
Transom1	Rear	1	0.98	14.99	90.0	1.00	0.00

Transom2	Entry 1							
	Rear	1	0.98	14.99	90.0	1.00	0.00	
	Entry 2							

Label	Type	#	Window Width (ft)	Window Height (ft)	Total Area (ft ²)	Window R	SHGC	ER*
Southeast Master Bed (P)	cadre en bois et contre-fenêtre	1	7.51	6.00	45.11	2.136	0.5753	14.8
Northeast Bed 3 (S)	cadre en métal et contre-fenêtre	1	2.49	4.99	12.43	1.410	0.5461	- 17.5
Doorlite	cadre en bois et contre-fenêtre	1	2.49	5.68	14.15	2.126	0.5188	10.7
Ensuite (P)	cadre en bois et contre-fenêtre	1	2.00	5.51	11.03	2.122	0.4976	9.2
Master Bed (S)	cadre en bois et contre-fenêtre	1	7.51	6.00	45.11	2.136	0.5753	14.8
Northwest Basement (DS) 2	cadre en bois et contre-fenêtre	1	4.92	2.00	9.85	2.111	0.4592	6.5
Main Bath (P)	Code2	1	2.00	2.99	5.98	5.049	0.3391	33.2
Southwest Basement (DS) 1	cadre en bois et contre-fenêtre	1	4.92	2.00	9.85	2.111	0.4592	6.5
Bed 2/ Hallway (P)	cadre en bois et contre-fenêtre	2	2.99	4.99	29.78	2.127	0.5249	11.5
Bed 2/ Hallway (S)	cadre en bois et contre-fenêtre	2	2.99	4.99	29.78	2.127	0.5249	11.5
Great Room (P)	cadre en bois et contre-fenêtre	1	4.99	6.00	29.94	2.134	0.5617	13.8

Great Room (S)	cadre en bois et contre-fenêtre	1	4.99	6.00	29.94	2.134	0.5617	13.8
Rear Doorlite	cadre en bois et contre-fenêtre	1	2.33	5.68	13.22	2.125	0.5131	10.3
Transom1	Glass Block	1	2.33	0.98	2.29	2.111	0.2613	-8.5
Transom2	Glass Block	1	2.33	0.98	2.29	2.111	0.2613	-8.5

*ER Window Energy Rating (ER 2009) estimated for actual dimensions, and Air tightness type: CSA - A3;
Leakage rate = 0.50 L/s.m²

Above grade fraction of wall area occupied by windows: 8.2 %

USER-DEFINED WINDOW CODES SCHEDULE

Code	Description	Window Type
Code2	wood frame window	Picture
Glass Block		Picture
Glass Block		Picture

USER-DEFINED WINDOW CODES: DATA

Code	RSI - Centre of Glass	RSI - Edge of Glass	RSI - Frame	Frame Ht mm	Centre of Glass SHGC
Code2	1.205	0.833	0.568	39.3	0.420
Glass Block	0.440	0.329	0.357	4.0	0.270
Glass Block	0.440	0.329	0.357	4.0	0.270

***** TYPE 2 USER DEFINED WINDOW CODES *****

Code Label	Description	Glazing Type	Fill Gas	Thermal Resistance	SHGC	Window Style	Low -E Coating	Frame Height
cadre en bois et contre_fenêtre		Double/double with 1 coat	Air	0.3750 R	0.5400	Double Hung	Clear	50.80
cadre en métal et contre_fenêtr		Double/double with 1 coat	Air	0.2630 R	0.5600	Double Hung	Clear	25.40
cadre en bois et contre_fenêtre		Double/double with 1 coat	Air	0.3750 R	0.5400	Double Hung	Clear	50.80
cadre en bois et contre_fenêtre		Double/double with 1 coat	Air	0.3750 R	0.5400	Double Hung	Clear	50.80
cadre en bois et contre_fenêtre		Double/double with 1 coat	Air	0.3750 R	0.5400	Double Hung	Clear	50.80
cadre en bois et contre_fenêtre		Double/double with 1 coat	Air	0.3750 R	0.5400	Double Hung	Clear	50.80
cadre en bois et contre_fenêtre		Double/double with 1 coat	Air	0.3750 R	0.5400	Double Hung	Clear	50.80
cadre en bois et contre_fenêtre		Double/double with 1 coat	Air	0.3750 R	0.5400	Double Hung	Clear	50.80
cadre en bois et contre_fenêtre		Double/double with 1 coat	Air	0.3750 R	0.5400	Double Hung	Clear	50.80
cadre en bois et contre_fenêtre		Double/double with 1 coat	Air	0.3750 R	0.5400	Double Hung	Clear	50.80
cadre en bois et contre_fenêtre		Double/double with 1 coat	Air	0.3750 R	0.5400	Double Hung	Clear	50.80

BUILDING PARAMETER DETAILS

CEILING COMPONENTS

	Construction Type	Code Type	Roof Slope	Heel Ht. (ft)	Section Area (ft ²)	R. Value (R)
Main Upper	Attic/gable	User specified	8.000/12	0.66	1138.82	49.68

MAIN WALL COMPONENTS

Label	Lintel Type	Fac. Dir	Number of Corn.	Number of Inter.	Height (ft)	Perim. (ft)	Area (ft²)	R. Value (R)
(1F) Fire Rated Type: User specified	N/A	N/A	2	10	9.09	42.81	389.10	16.98
(1F) Fire Rated Dropped Type: User specified	N/A	N/A	0	1	10.07	21.26	214.13	16.98
(1F) Main Type: User specified	N/A	N/A	0	0	9.09	26.35	239.42	16.81
(1F) Main Dropped Type: User specified	N/A	N/A	2	1	10.07	21.00	211.49	16.81
(2F) Fire Rated Type: User specified	N/A	N/A	8	18	8.07	100.10	807.88	16.98
(2F) Main Type: User specified	N/A	N/A	0	4	8.07	57.91	467.36	16.81
Garage to House Type: User specified	N/A	N/A	0	4	9.09	16.01	145.50	> 19.08
Tall Wall Type: User specified	N/A	N/A	0	0	15.81	19.16	302.99	> 19.53
(1F) Dropped Floor Header Type: User specified		N/A	4	4	0.82	50.00	41.01	22.83
(1F) Main Floor Header Type: User specified		N/A	4	4	0.98	61.42	60.45	22.83
(2F) Main Floor Header Type: User specified		N/A	4	4	0.98	141.01	138.79	22.83
Garage to House Floor Header Type: User specified		N/A	4	4	0.98	16.01	15.76	> 24.64

> Indicates that the component is adjacent to an enclosed unconditioned space.

EXPOSED FLOORS

Label	Floor Code Type	Area (ft²)	R. Value (R)
Over Garage	User specified	299.77	> 31.97

> Indicates that the component is adjacent to an enclosed unconditioned space.

DOORS

Label	Type	Height (ft)	Width (ft)	Gross Area (ft²)	R. Value (R)
Front Entry Loc: (1F) Main	User specified	6.82	2.99	20.37	3.86
Garage to House Entry Loc: Garage to	User specified	6.82	2.66	18.14	> 5.62

House

Rear Entry 1	User specified	7.84	2.66	20.84	3.80
Loc: (1F) Main					
Dropped					
Rear Entry 2	User specified	7.84	2.66	20.84	3.80
Loc: (1F) Main					
Dropped					

> Indicates that the component is adjacent to an enclosed unconditioned space.

FOUNDATIONS

Foundation Name:	Dropped Wall	Volume:	2442.0 ft ³
Foundation Type:	Basement	Opening to Main Floor:	16.79 ft ²
Data Type:	Library		
Total Wall Height:	8.23 ft	Non-Rectangular	
Depth Below Grade:	6.23 ft	Floor Perimeter:	115.91 ft
		Floor Area:	296.55 ft ²
Interior wall type:	User specified	R-value:	11.87 R
Exterior wall type:	User specified	R-Value:	0.00 R
Number of corners :	2		
Lintel type:	N/A		
Added to slab type :	N/A	R-Value:	0.00 R
Floors Above	User specified	R-Value:	3.69 R
Found.:			

Exposed areas for: Dropped Wall
Exposed Perimeter: 115.91 ft

Configuration: BCIN_1
 - concrete walls and floor
 - interior surface of wall insulated over full-height
 - any first storey construction type

Foundation Name:	Foundation	Volume:	4077.6 ft ³
Foundation Type:	Basement	Opening to Main Floor:	16.79 ft ²
Data Type:	Library		
Total Wall Height:	8.99 ft	Non-Rectangular	
Depth Below Grade:	6.23 ft	Floor Perimeter:	115.91 ft
		Floor Area:	453.59 ft ²
Interior wall type:	User specified	R-value:	0.00 R
Exterior wall type:	User specified	R-Value:	0.00 R
Number of corners :	2		
Lintel type:	N/A		
Added to slab type :	N/A	R-Value:	0.00 R
Floors Above	User specified	R-Value:	3.69 R
Found.:			

Exposed areas for: Foundation
Exposed Perimeter: 65.91 ft

Configuration: BCNN_1
 - concrete walls and floor
 - no insulation
 - first storey brick veneer placed directly on basement's concrete walls

FOUNDATION CODE SCHEDULE

FOUNDATION FLOOR HEADER COMPONENTS

Label	Lintel Type	Fac. Dir	Number of Corn.	Number of Inter.	Height (ft)	Perim. (ft)	Area (ft ²)	R. Value (R)
BW hdr-01 (Location:Dropped Wall) Type: 0000000000	N/A	N/A	4	4	0.75	123.23	92.99	15.27

ROOF CAVITY INPUTS

Gable Ends		Total Area:	253.08 ft ²
Sheathing Material	Plywood/Part. bd 9.5 mm (3/8 in)		0.47 R
Exterior Material:	Hollow metal/vinyl cladding		0.62 R
Sloped Roof		Total Area:	738.63 ft ²
Sheathing Material	Plywood/Part. bd 12.7 mm (1/2 in)		0.63 R
Exterior Material:	Asphalt shingles		0.44 R
Total Cavity Volume:	1293.1 ft ³	Ventilation Rate:	0.50 ACH/hr

BUILDING ASSEMBLY DETAILS

Label	Construction Code	Nominal (R)	System (R)	Effective (R)
-------	-------------------	-------------	------------	---------------

BUILDING PARAMETERS SUMMARY
ZONE 1 : Above Grade

Component	Area ft ² Gross	Area ft ² Net	Effective (R)	Heat Loss Mil.BTU	% Annual Heat Loss
Ceiling	1138.82	1138.82	49.68	5.80	3.50
Main Walls	3033.89	2714.61	17.72	41.80	25.25
Doors	80.18	48.23	4.11	3.41	2.06
Exposed floors	299.77	299.77	31.97	2.50	1.51
Southeast Windows	45.11	45.11	2.14	6.13	3.70
Northeast Windows	82.73	82.73	1.98	12.13	7.33
Northwest Windows	5.98	5.98	5.05	0.34	0.21
Southwest Windows	137.24	137.24	2.13	18.71	11.30
ZONE 1 Totals:				90.83	54.85

INTER-ZONE Heat Transfer : Floors Above Basement

Area ft ² Gross	Area ft ² Net	Effective (R)	Heat Loss Mil.BTU
750.14	750.14	3.691	43.08

ZONE 2 : Basement

Component	Area ft ² Gross	Area ft ² Net	Effective (R)	Heat Loss Mil.BTU	% Annual Heat Loss
Walls above grade	413.62	393.93	-	25.70	15.52
Northwest windows	9.85	9.85	2.11	0.96	0.58
Southwest windows	9.85	9.85	2.11	0.96	0.58
Basement floor header	92.99	92.99	15.27	0.28	0.17
Below grade foundation	1883.56	1883.56	-	22.13	13.37
ZONE 2 Totals:				50.03	30.22

Air Leakage and Mechanical Ventilation

House Volume	Air Change	Heat Loss Mil.BTU	% Annual Heat Loss
25080.48 ft ³	0.156 ACH	24.723	14.93

AIR LEAKAGE AND MECHANICAL VENTILATION

Building Envelope Surface Area: 6862.65 ft²

Air Leakage Test Results at 50 Pa. 3.20 ACH
(0.2 in H₂O) =

Equivalent Leakage Area @ 10 Pa 131.53 in²
=

Terrain Description

			Height (ft)
@ Weather Station :	Open flat terrain, grass	Anemometer:	32.8
@ Building site :	Suburban, forest	Height of the highest ceiling:	18.0

Local Shielding:

Walls:	Very heavy
Flue :	Light

Leakage Fractions-

Ceiling:	0.200
Walls:	0.650
Floors:	0.150

Normalized Leakage Area @ 10 Pa: 0.0192 in²/ft²

Estimated Airflow to cause a 5 Pa Pressure Difference: 286 cfm

Estimated Airflow to cause a 10 Pa Pressure Difference: 449 cfm

F326 VENTILATION REQUIREMENTS

Kitchen, Living Room, Dining Room	3 rooms @ 2.4 cfm: 31.8 cfm
Utility Room	1 rooms @ 2.4 cfm: 10.6 cfm
Bedroom	1 rooms @ 4.7 cfm: 21.2 cfm
Bedroom	1 rooms @ 10.6 cfm: 10.6 cfm
Bathroom	1 rooms @ 2.4 cfm: 10.6 cfm
Basement Rooms	21.2 cfm

CENTRAL VENTILATION SYSTEM

System Type: HRV
Manufacturer:

Model Number:**Fan and Preheater Power at 32.0 °F:** 62 Watts**Fan and Preheater Power at -13.0 °F:** 62 Watts**Preheater Capacity:** 0 Watts**Sensible Heat Recovery Efficiency at 32.0 °F** 60%**Sensible Heat Recovery Efficiency at -13.0 °F** 60%**Total Heat Recovery Efficiency in Cooling Mode** 25%**Low Temperature Ventilation Reduction:** 0%**Low Temperature Ventilation Reduction:** 0 cfm (0.0%)
Airflow Adjustment

Vented combustion appliance depressurization limit: 5.00 Pa.

Ventilation Supply Duct

Location:	Main floor	Type:	Flexible
Length:	4.9 ft	Diameter:	6.0 in
Insulation:	4.0 R	Sealing Characteristics:	Sealed

Ventilation Exhaust Duct

Location:	Main floor	Type:	Flexible
Length:	4.9 ft	Diameter:	6.0 in
Insulation:	4.0 R	Sealing Characteristics:	Sealed

SECONDARY FANS & OTHER EXHAUST APPLIANCES

	Control	Supply (cfm)	Exhaust (cfm)
Other Fans	Continuous	0.00	7.95
Dryer	Continuous	-	3.16

Dryer is vented outdoors**Rated Fan Power** 2.85 Watts**NEW ERS VENTILATION DATA****Whole House Systems****Air Distribution/circulation type:** Forced air heating ductwork**Air Distribution/circulation fan power:** 0.00 Watts

Operation schedule: 480.00 min/day

System # 1 Type: HRV

Manufacturer:

Model:

Airflow Supply Rate: 57.21 cfm **Exhaust:** 57.21 cfm **Fan Power:** 62.00 Watts

Supplementary Systems

System # 1 Type: Dryer

Manufacturer:

Model:

Airflow Supply Rate: 0.00 cfm **Exhaust:** 80.52 cfm **Fan Power:** 0.00 Watts

Operation schedule: 56.50 min/day

System # 2 Type: Range hood

Manufacturer:

Model:

Airflow Supply Rate: 0.00 cfm **Exhaust:** 158.92 cfm **Fan Power:** 57.00 Watts

Operation schedule: 72.00 min/day

AIR LEAKAGE AND MECHANICAL VENTILATION SUMMARY

F326 Required continous ventilation: 105.944 cfm (0.25 ACH)

Central Ventilation Supply Rate (): 57.210 cfm (0.14 ACH)

Other Continuous Supply Flow Rates: 0.000 cfm (0.00 ACH)

Other Continuous Exhaust Flow Rates: 7.946 cfm (0.02 ACH)

Total house ventilation is Balanced

Gross Air Leakage and Mechanical Ventilation Energy Load: 22.740 Mil.BTU

Seasonal Heat Recovery Ventilator Efficiency: 58.836 %

Estimated Ventilation Electrical Load: 0.580 Mil.BTU

Heating Hours:

Estimated Ventilation Electrical Load: 0.037 Mil.BTU

Non-Heating Hours:

Net Air Leakage and Mechanical Ventilation Load: 25.013 Mil.BTU

VENTILATION REQUIREMENTS

Use:	Flow rate
ACH:	0.00
Supply:	0.00 cfm
Exhaust:	0.00 cfm

SPACE HEATING SYSTEM

PRIMARY Heating Fuel:	Natural Gas
Equipment:	Condensing furnace/boiler
Manufacturer:	Wizard SPH man
Model:	
Calculated* Output Capacity:	69948.89 BTU/h
* Design Heat loss X 1.10 + 0.5 kW	

AFUE:	96.00
Steady State Efficiency:	98.04
Fan Mode:	Two Speed
ECM Motor:	No
Low Speed Fan Power:	318 watts
High Speed Fan Power:	398 watts

DOMESTIC WATER HEATING SYSTEM

PRIMARY Water Heating Fuel:	Natural gas		
Water Heating Equipment:	Direct vent (sealed)		
Energy Factor:	0.670		
Manufacturer:			
Model:			
Tank Capacity:	41.6 Imp Gal	Tank Blanket Insulation:	0.0 R
Tank Location:	Basement		
Pilot Energy :	0.0 BTU/h	Flue Diameter:	0.0 In

ANNUAL DOMESTIC WATER HEATING SUMMARY

Daily Hot Water Consumption: 56.5 Imp Gal
 Hot Water Temperature: 131.0 °F
 Estimated Domestic Water Heating Load: 18.513 Mil.BTU

Primary Domestic Water Heating Energy Consumption: 27.040 Mil.BTU
 Primary System Seasonal Efficiency: 68.5%

ANNUAL SPACE HEATING SUMMARY

Gross Space Heat Loss: 165.583 Mil.BTU

Gross Space Heating Load: 164.773 Mil.BTU
 Usable Internal Gains: 35.342 Mil.BTU
 Usable Internal Gains Fraction: 21.3 %
 Usable Solar Gains: 29.687 Mil.BTU
 Usable Solar Gains Fraction: 17.9 %
 Auxiliary Energy Required: 99.745 Mil.BTU

Space Heating System Load: 99.745 Mil.BTU
 Furnace/Boiler Seasonal efficiency: 96.3 %
 Furnace/Boiler Annual Energy Consumption: 99.799 Mil.BTU

DESIGN SPACE HEATING AND COOLING LOADS

Design Heat Loss* at -23.4 °F (2.51 BTU/h / Ft³): 63055 BTU/h
 Design Cooling Load* for July at (81.3 ° F): 19649 BTU/h

* Please refer to notes at the end of this report.

BASE LOADS SUMMARY

	kwh/day	Annual kWh
Interior Lighting	2.60	949.00
Appliances	7.82	2852.87
Other	9.70	3540.50

Exterior Use	0.90	328.50
HVAC Fans		
HRV/Exhaust	0.56	205.99
Space Heating	7.94	2898.30
Space Cooling	0.00	0.00
Total Average Electrical Load	29.52	10775.16

FAN OPERATION SUMMARY (kWh)

Hours	HRV/Exhaust Fans	Space Heating	Space Cooling
Heating	190.0	556.3	0.0
Neither	16.0	2342.0	0.0
Cooling	0.0	0.0	0.0
Total	206.0	2898.3	

ENERGY CONSUMPTION SUMMARY REPORT

Estimated Annual Space Heating Energy Consumption	= 107296.65 MJ	= 29804.62 kWh
Ventilator Electrical Consumption: Heating Hours	= 612.38 MJ	= 170.11 kWh
Estimated Annual DHW Heating Energy Consumption	= 28529.20 MJ	= 7924.78 kWh
ESTIMATED ANNUAL SPACE + DHW ENERGY CONSUMPTION	= 136438.23 MJ	= 37899.51 kWh
Estimated Greenhouse Gas Emissions	15.607 tonnes/year	

ESTIMATED ANNUAL FUEL CONSUMPTION SUMMARY

Fuel	Space Heating	Space Cooling	DHW Heating	Baseloads	Ventilation	Total
Natural Gas (MCF)	99.8	0.0	27.0	0.0	0.0	126.8
Electricity (kWh)	556.3	0.0	0.0	10012.9	206.0	10775.2

ESTIMATED ANNUAL FUEL CONSUMPTION COSTS

Fuel Costs Library = Embedded

RATE	Electricity (Ottawa97)	Natural Gas (Ottawa08)	Oil (Ottawa08)	Propane (Ottawa08)	Wood (Sth Ont)	Total
\$	965.52	2046.01	0.00	0.00	0.00	3011.53

Fuel Costs Library Listing

Filename = Embedded

Record # 1	Fuel: Electricity		
Rate ID = Ottawa97	Hydro Rate Block		
Rate Block		Dollars	Charge
	kWhr	Per kWhr	(\$)
Minimum	0.0		10.000
1	250.0	0.0999	
2	99999.0	0.0702	

Record # 2	Fuel: Natural Gas		
Rate ID = Ottawa08	Gas Rate Block		
Rate Block		Dollars	Charge
	m3	Per m3	(\$)
Minimum	0.0		14.000
1	30.0	0.5338	
2	85.0	0.5277	
3	170.0	0.5229	
4	99999.0	0.5194	

Record # 3	Fuel: Oil		
Rate ID = Ottawa08	Oil Rate Block		
Rate Block		Dollars	Charge
	Litre	Per Litre	(\$)
Minimum	0.0		0.000
1	99999.0	1.1750	

Record # 4	Fuel: Propane		
Rate ID = Ottawa08	Propane Rate Block		
Rate Block		Dollars	Charge
	Litre	Per Litre	(\$)
Minimum	0.0		0.000
1	99999.0	0.7200	

Record # 5	Fuel: Wood		
Rate ID = Sth Ont	Cord Rate		
Rate Block		Dollars	Charge
	Cord	Per Cord	(\$)
Minimum	0.0		0.000
1	99999.0	210.0000	

MONTHLY ENERGY PROFILE

Month	Energy Load (Mil.BTU)	Internal Gains (Mil.BTU)	Solar Gains (Mil.BTU)	Aux. Energy (Mil.BTU)	HRV Eff. %
Jan	24.936	2.936	2.274	19.726	58.8
Feb	21.370	2.674	2.837	15.859	58.8
Mar	20.066	3.017	3.922	13.128	58.8
Apr	12.823	3.000	3.389	6.434	58.9
May	8.272	3.161	3.053	2.059	58.3
Jun	5.296	3.063	1.968	0.265	59.1
Jul	3.266	2.319	0.947	0.000	59.1
Aug	4.910	3.119	1.698	0.094	59.0
Sep	7.812	3.074	2.704	2.034	59.0
Oct	12.873	3.112	2.614	7.147	58.9
Nov	18.740	2.923	2.270	13.547	58.8
Dec	24.408	2.945	2.010	19.453	58.8
Ann	164.773	35.342	29.687	99.745	58.8

FOUNDATION ENERGY PROFILE

Month	Heat Loss (Mil.BTU)				Total
	Crawl Space	Slab	Basement	Walkout	
Jan	0.000	0.000	0.000	0.000	0.000
Feb	0.000	0.000	0.000	0.000	0.000
Mar	0.000	0.000	0.000	0.000	0.000
Apr	0.000	0.000	0.000	0.000	0.000
May	0.000	0.000	0.000	0.000	0.000
Jun	0.000	0.000	0.000	0.000	0.000
Jul	0.000	0.000	0.000	0.000	0.000
Aug	0.000	0.000	0.000	0.000	0.000
Sep	0.000	0.000	0.000	0.000	0.000
Oct	0.000	0.000	0.000	0.000	0.000
Nov	0.000	0.000	0.000	0.000	0.000
Dec	0.000	0.000	0.000	0.000	0.000
Ann	0.000	0.000	0.000	0.000	0.000

FOUNDATION TEMPERATURES & VENTILATION PROFILE

Month	Temperature (Deg °F)			Air Change Rate		Heat Loss (Mil.BTU)
	Crawl Space	Basement	Walkout	Natural	Total	

Jan	0.0	53.3	0.0	0.183	0.225	4.472
Feb	0.0	53.9	0.0	0.176	0.218	3.679
Mar	0.0	56.1	0.0	0.156	0.197	3.220
Apr	0.0	60.1	0.0	0.113	0.155	1.637
May	0.0	63.8	0.0	0.080	0.122	0.860
Jun	0.0	66.2	0.0	0.056	0.098	0.430
Jul	0.0	68.0	0.0	0.042	0.084	0.282
Aug	0.0	67.3	0.0	0.047	0.089	0.387
Sep	0.0	64.7	0.0	0.075	0.117	0.806
Oct	0.0	61.1	0.0	0.110	0.152	1.644
Nov	0.0	57.1	0.0	0.152	0.193	2.957
Dec	0.0	54.0	0.0	0.181	0.223	4.349
Ann	0.0	60.5	0.0	0.114	0.156	24.723

SPACE HEATING SYSTEM PERFORMANCE

Month	Space Heating Load (Mil.BTU)	Furnace Input (Mil.BTU)	Pilot Light (Mil.BTU)	Indoor Fans (Mil.BTU)	Heat Pump Input (Mil.BTU)	Total Input (Mil.BTU)	System Cop
Jan	19.726	19.737	0.000	0.883	0.000	20.620	0.981
Feb	15.859	15.868	0.000	0.790	0.000	16.658	0.981
Mar	13.128	13.135	0.000	0.857	0.000	13.993	0.981
Apr	6.434	6.437	0.000	0.806	0.000	7.243	0.981
May	2.059	2.060	0.000	0.815	0.000	2.876	0.981
Jun	0.265	0.265	0.000	0.783	0.000	1.048	0.981
Jul	0.000	0.000	0.000	0.808	0.000	0.808	0.000
Aug	0.094	0.094	0.000	0.808	0.000	0.902	0.981
Sep	2.034	2.035	0.000	0.789	0.000	2.824	0.981
Oct	7.147	7.151	0.000	0.835	0.000	7.986	0.981
Nov	13.547	13.554	0.000	0.833	0.000	14.387	0.981
Dec	19.453	19.464	0.000	0.882	0.000	20.345	0.981
Ann	99.745	99.799	0.000	9.889	0.000	109.689	0.963

MONTHLY ESTIMATED ENERGY CONSUMPTION BY DEVICE (Mil.BTU)

Month	Space Heating		DHW Heating		Lights & Appliances	HRV & FANS	Air Conditioner
	Primary	Secondary	Primary	Secondary			
Jan	19.737	0.000	2.426	0.000	2.223	0.943	0.000

Feb	15.868	0.000	2.202	0.000	2.008	0.844	0.000
Mar	13.135	0.000	2.412	0.000	2.223	0.917	0.000
Apr	6.437	0.000	2.275	0.000	2.151	0.864	0.000
May	2.060	0.000	2.279	0.000	2.223	0.875	0.000
Jun	0.265	0.000	2.142	0.000	2.151	0.841	0.000
Jul	0.000	0.000	2.174	0.000	2.223	0.867	0.000
Aug	0.094	0.000	2.154	0.000	2.223	0.868	0.000
Sep	2.035	0.000	2.112	0.000	2.151	0.847	0.000
Oct	7.151	0.000	2.240	0.000	2.223	0.895	0.000
Nov	13.554	0.000	2.240	0.000	2.151	0.891	0.000
Dec	19.464	0.000	2.384	0.000	2.223	0.941	0.000
Ann	99.799	0.000	27.040	0.000	26.174	10.592	0.000

ESTIMATED FUEL COSTS (Dollars)

Month	Electricity	Natural Gas	Oil	Propane	Wood	Total
Jan	82.55	341.16	0.00	0.00	0.00	423.71
Feb	76.09	280.95	0.00	0.00	0.00	357.04
Mar	82.03	243.84	0.00	0.00	0.00	325.87
Apr	79.46	143.33	0.00	0.00	0.00	222.79
May	81.17	78.84	0.00	0.00	0.00	160.01
Jun	78.98	50.15	0.00	0.00	0.00	129.13
Jul	81.01	46.67	0.00	0.00	0.00	127.68
Aug	81.01	47.77	0.00	0.00	0.00	128.79
Sep	79.11	76.00	0.00	0.00	0.00	155.11
Oct	81.57	153.30	0.00	0.00	0.00	234.87
Nov	80.01	247.48	0.00	0.00	0.00	327.49
Dec	82.53	336.52	0.00	0.00	0.00	419.04
Ann	965.52	2046.01	0.00	0.00	0.00	3011.53

The calculated heat losses and energy consumptions are only estimates, based upon the data entered and assumptions within the program. Actual energy consumption and heat losses will be influenced by construction practices, localized weather, equipment characteristics and the lifestyle of the occupants.